

BEAR BRANCH PHASE 1 STREAM RESTORATION

December 15, 2020

Tonight's Agenda

- □ Background, Location & Timeline
- □ Project Team Introductions
- □ The Urban Watershed Problem
- Why Stream Restorations?
- Design Overview
- □ Restoration Examples Around Town
- □ Next Steps and Q&A Session
- □ One-on-One Discussion, Individual Questions

Project Background

■ History:


5th Stream Restoration in Vienna

□ Purpose:

Restore natural stream and stabilize steep, eroded stream banks using natural channel design techniques.

□ Funding:

- 50% Virginia Department of Environmental Quality Grant
- 50% Fairfax County
 Stormwater Fees



Project Location & Timeline

□ Location:
Cottage St SW to I-66
(1,900 linear feet)

□ <u>Estimated Timeline</u>:

- July 2020 Council Approved Engineering Design Contract
- December 2020 Concept Design Meeting
- March 2021 Detailed Design Meeting
- Spring 2021 Public Bid for Construction Contract
- Summer 2021 Begin Construction (12 months)



Project Team

- Town of Vienna
 - Michael Gallagher, P.E., Director of Public Works
 - Christine Horner, P.E., Water Quality Engineer

Email: Christine.Horner@viennava.gov

Phone: 703-319-8630





Design and Engineering Consultants




- Fairfax County Stormwater Planning Division
- Virginia Department of Environmental Quality Clean Water Financing and Assistance Program






The Urban Watershed Problem



Source: The Federal Interagency Stream Restoration Working Group

The Urban Watershed Problem




1953 – Bear Branch



2019 - Bear Branch


■ Bank Erosion and Stability





■ Bank Erosion and Stability





■ Water Quality and Ecosystem Impacts



□ Erosion Undermines Trees





■ Downstream Blockages





□ Prevent Private Property Loss





■ Safety and Protects Infrastructure





Design Overview

- □ 1,900 Linear Feet of Stream Restoration
- □ Re-Use of On-Site Materials
- □ Natural Channel Design:
 Rock Toe, Log Vanes, Toe-Wood, Cross Vanes,
 Constructed Riffles and Pools
- □ Re-Planting of Riparian Buffer, Trees and Shrubs

□ Step-Pools / Plunge Pools



Piney Branch (Mill St NE)



Wolftrap Creek (Wildwood Park)

□ Constructed Riffle



Piney Branch (Mill St NE)

Wolftrap Creek (Wildwood Park)

□ Cross Vanes



Wolftrap Creek (Wildwood Park)



Hunters Branch (Vienna Dog Park – Moorefield Park)

■ Toe Wood




Wolftrap Creek (Wildwood Park)



Wolftrap Creek (Wildwood Park)

Proposed Design from Cottage St SW to Ross Dr SW



Proposed Design from Ross Dr SW to I-66



□ Wolftrap Creek (Wildwood Park)





□ Wolftrap Creek (Wildwood Park)





□ Piney Branch (Mill St NE)





□ Piney Branch (Mill St NE)





Next Steps

- Anticipated Timeline
 - January 8, 2021 Citizen Comment Period Closes
 - March 2021 Detailed Design Meeting
 - Spring 2021 Public Bid for Construction Contract
 - Summer 2021 Begin Construction for 12 Months
- Next Steps
 - Compile Citizen Comments via Email
 Christine.Horner@viennava.gov
 - Create a Comment and Response Table
 - Incorporate Design Changes from Feedback
 - Proceed with Final Design for Next Public Meeting

Questions?

Contact Information:

Christine Horner

Town of Vienna – Department of Public Works

Christine.Horner@viennava.gov

703-319-8630

Thank you for your interest in Bear Branch Phase I Stream Restoration.